

**SUGAR GROVE AREA OFFICE
BUNDLED SITES CHARACTERIZATION REPORT/
RESPONSE ACTION WORK PLAN**

FAIRFIELD COUNTY, OHIO

29 March 2000

REVISION NO. 1
6 September 2000

Prepared For
COLUMBIA GAS TRANSMISSION

By:
CIVIL & ENVIRONMENTAL CONSULTANTS, INC
AND
ENVIRONMENTAL STANDARDS, INC.

Site Background Concentration – Three background soil samples (SGA-ASU009-70001 through SGA-ASU011-70001) were collected during the site characterization. All three samples were analyzed for Table 1 metals, PAHs, PCBs, and VOCs. PCBs, VOCs, and PAHs were not detected. Five Table 1 metals were detected. Background concentrations for these five metals have been calculated in Appendix H (Background Worksheet) and are listed below:

- Arsenic – 37.4 mg/kg
- Barium – 127.3 mg/kg
- Cadmium – 22.1 mg/kg
- Chromium – 18 mg/kg
- Nickel – 28.8 mg/kg

PRA No. 4 - Former Rush Creek Dump – Soil boring SGA-ASB005 located in the suspected center of this former dump had detectable characterization constituents from subsurface samples greater than the CALs and/or site background concentrations. Sample SGA-ASB005-70001 (2.0 feet bgs) had six constituents detected greater than the CALs and/or site background concentrations, and sample SGA-ASB005-70002 (5.0 feet bgs) had eleven constituents greater than the CALs and/or site background concentrations.

Sample results for CAL/background exceedances for SGA-ASB005-70001 are as follows:

- PCBs Detected: 1.8 mg/kg CAL 1.0 mg/kg
- PAHs Detected:
 - benzo(a)anthracene 11 mg/kg CAL 0.87 mg/kg
 - benzo(a)pyrene 5.9 mg/kg CAL 0.087 mg/kg
 - benzo(b)fluoranthene 9.9 mg/kg CAL 0.87 mg/kg
 - benzo(k)fluoranthene 11 mg/kg CAL 8.7 mg/kg
 - indeno(1,2,3-c,d)pyrene 1.6 mg/kg CAL 0.87 mg/kg

Sample results for CAL/background exceedances for SGA-ASB005-70002 are as follows:

- PCBs Detected: 12 mg/kg CAL 1.0 mg/kg
- PAHs Detected:
 - benzo(a)anthracene 150 mg/kg CAL 0.87 mg/kg
 - benzo(a)pyrene 110 mg/kg CAL 0.087 mg/kg
 - benzo(b)fluoranthene 120 mg/kg CAL 0.87 mg/kg
 - benzo(k)fluoranthene 75 mg/kg CAL 8.7 mg/kg
 - chrysene 130 mg/kg CAL 87.0 mg/kg
 - ideno(1,2,3-c,d)pyrene 86 mg/kg CAL 0.87 mg/kg
- Metals Detected:
 - Antimony 2,140 mg/kg CAL 31.0 mg/kg
 - Arsenic 38.9 mg/kg CAL 0.43 mg/kg BG 37.4 mg/kg
 - Cadmium 113 mg/kg CAL 39.0 mg/kg BG 22.0 mg/kg
 - Lead 1,650 mg/kg CAL 400.0 mg/kg

PRA No. 5 - Former Dump (Beneath Current Telecommunications Building) – Soil borings SGA-ASB008 and SGA-ASB011 were located in opposite quadrants of a suspected dump beneath the current telecommunications building (Figure 3). Each boring had detectable characterization constituents greater than the CALs and/or site background concentrations. Soil sample SGA-ASB008-40001 (0 - 1.0 feet bgs) had five constituents detected greater than the CALs and/or site background concentrations; sample SGA-ASB011-40001 (0 - 1.0 feet bgs) had two constituents greater than the CAL and/or background; and sample SGA-ASB011-70001 (2.5 feet bgs) had five constituents greater than the CALs and/or site background concentrations.

4.3 PRAs Requiring Further Evaluation

Based on the results of this characterization effort, the following PRAs are proposed for further evaluation:

- PRA #4 Former Rush Creek Dump
- PRA #5 Former Dump (Beneath Current Telecommunications Building)
- PRA #12 Dry Well

4.4 Evaluation of Selected PRAs and Site Areas

A detailed description of the risk-based evaluation process is provided in Appendix F.

4.4.1 Evaluation of Soil

The first two steps of the site evaluation process depicted in Figure 1 of Appendix F, comparison to residential CALs was conducted in Section 3. The next step of the process is to evaluate the site data using industrial Response Action Levels (RALs), where appropriate. Access to the Sugar Grove site is not restricted, and residences are close by. Therefore, the site will not be evaluated under an industrial use scenario.


The fourth step of the process is to calculate site concentrations (as described in Section 3.1 and in detail in Appendix F). Because unrestricted access is assumed under the future use scenario, site concentrations for each relevant constituent and medium have been calculated using all data for the site. The calculations are presented in Appendix H.

Site concentrations in soil for the remaining constituents identified in the PRAs listed in section 4.3 are as follows:

<u>Constituent</u>	<u>Site Concentration (mg/kg)</u>	<u>CAL (mg/kg)</u>
• Antimony	27.8	31.0
• Arsenic	14.5	0.43
• Cadmium	21.8	39.0
• Lead	91.4	400.0
• Benzo(a)anthracene	4.2	0.87
• Benzo(a)pyrene	3.2	0.087
• Benzo(b)fluoranthene	4.7	0.87
• Benzo(k)fluoranthene	3.0	8.7
• Chrysene	4.2	87.0
• Dibenzo(a,h)anthracene	0.7	0.087
• Indeno(1,2,3-c,d)pyrene	2.5	0.87

Site concentrations for Antimony, Cadmium, Lead, Benzo(k)fluoranthene, and Chrysene in soil are less than the residential CALs. Therefore, a response action is not recommended for these constituents. However, the site concentrations of Arsenic, Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene and Indeno(1,2,3-c,d)pyrene in soil are greater than the CALs, and a response action is recommended for these constituents.

P:\PROJECTS\98320\300\DWG\2FG-1.dwg J.KEELING - JULY 09, 1999 - 12:59:15 XREFS:



1000 500 0 500 1000 2000
SCALE: 1"=2000'



SOURCE: USGS 7.5 MINUTE QUADRANGLE ROCKBRIDGE, OHIO, PHOTO 1992.



Civil & Environmental Consultants, Inc.
Cincinnati, OH
(513) 985-0226 • (800) 759-5614
Pittsburgh, PA • Columbus, OH • Nashville, TN

Site Location Map

COLUMBIA GAS TRANSMISSION CORP.
Sugar Grove Area Office

Sugar Grove, Fairfield County, Ohio

DWN. BY: JK
CHKD. BY: MJW


SCALE:
AS SHOWN

DATE:
JULY 1999

PROJECT NO:
98320


FIGURE NO:
1

G:\PROJECTS\98320\0360 - SUGAR GROVE\15CRGV-2.dwg JDC - MARCH 29, 2000 - 15:12:08 XREFS:



NOTES:

- 1) THE GROUNDWATER FLOW DIRECTION PRESENTED IS NOT BASED ON THE COLLECTION OF FIELD DATA AND THUS MAY NOT REFLECT ACTUAL CONDITIONS.

 Civil & Environmental Consultants, Inc. Cincinnati, OH (513) 985-0226 • (800) 759-5614 Pittsburgh, PA • Columbus, OH • Indianapolis, IN • Nashville, TN			Sample Locations Map	
DWN. BY:JK CHKD. BY:MJW			COLUMBIA GAS TRANSMISSION CORPORATION Sugar Grove Area Office	
SCALE: 1" = 200'			Sugar Grove, Ohio	
DATE: JULY 1999			PROJECT NO.: 98320	FIGURE NO: 2

	2.5	5.0
PCB	1.8	12.0
Sb	—	2140.0
As	—	38.9
Cd	—	113.0
Pb	—	1650.0
baa	11.0	150.0
bap	5.9	110.0
bbf	9.9	120.0
bkf	11.0	120.0
c	—	75.0
icp	1.6	86.0

NOTE:
FRAC TANK DRAINAGE CHANNEL
WATER & SEDIMENT SAMPLE LOCATION.

LEGEND

- ASU004 AT DEPTH SAMPLE LOCATION(>1')
- ASB011 SURFACE(0-1') & AT DEPTH(>1') SAMPLE LOCATION
- ASS009 SURFACE/SEDIMENT(0-1') SAMPLE LOCATION
- ASW003 SEDIMENT/SURFACE WATER LOCATION
- ASD003 GROUNDWATER SAMPLE
- AWP001 WIPE SAMPLES LOCATIONS
- ASU009 BACKGROUND SAMPLE LOCATION (TABLE 1 ANALYSIS)
- ASS004 BACKGROUND SAMPLE LOCATION (METALS ANALYSIS)

- PROPERTY LINE
- FENCE
- DRAINAGE AREA
- DRAINAGE CHANNEL/ON-SITE STREAM (INTERMITTANT)
- DRAINAGE CHANNEL/ON-SITE STREAM (PERENNIAL)
- ELECTRICAL UTILITIES
- STORM DRAIN
- GAS UTILITY
- GROUNDWATER FLOW DIRECTION
- SLOPE DIRECTION
- FORMER/REMOVED STRUCTURE(S)

- SGA PREFIX TO ALL SAMPLE LOCATIONS
- PCB POLYCHLORINATED BIPHENYLS
- Sb ANTIMONY
- As ARSENIC
- Cd CADMIUM
- Pb LEAD
- baa BENZO (a) ANTHRACENE
- bap BENZO (a) PYRENE
- bbf BENZO (b) FLUORANTHENE
- bkf BENZO (k) FLUORANTHENE
- c CHRYSENE
- icp IDENO (1,2,3-c,d) PYRENE
- daa DIBENZO (a,h) ANTHRACENE

RESULTS IN
SOIL/SEDIMENT mg/kg

NOTES:

- 1) THE GROUNDWATER FLOW DIRECTION PRESENTED IS NOT BASED ON THE COLLECTION OF FIELD DATA AND THUS MAY NOT REFLECT ACTUAL CONDITIONS.



Civil & Environmental Consultants, Inc.

9912 Carver Road
Cincinnati, OH 45242
(513) 985-0226 • (800) 759-5614
Pittsburgh, PA • Columbus, OH • Indianapolis, IN • Nashville, TN

COLUMBIA GAS TRANSMISSION
CORPORATION
Sugar Grove Area Office
Sugar Grove, Ohio

DATE: MAR. 2000	APPROVED BY: BJF	DWN BY: JK
SCALE: 1"= 100'		CHKD. BY: CST/NJF
Sample Results Which Exceed CALs and/or Background		SHEET 1 OF 1 DRAWING NUMBER 3

Table 4
Summary of Analytical Results

		PRA	0					
		PRA Description	RANDOM PCB					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASS007-40001	SGA-ASS008-40001		SGA-ASS009-40001		
		Depth - ft bgs	0 - .5	0 - .5		0 - .5		
		Collected Date	06/24/98	06/24/98		06/24/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000						
	ETHYL BENZENE	7800						
	XYLENES (TOTAL)	1000000						
	ACETONE	7800						
BNA	NAPHTHALENE	1600						
	ACENAPHTHENE	4700						
	FLUORENE	3100						
	PHENANTHRENE	23000						
	ANTHRACENE	23000						
	FLUORANTHENE	3100						
	PYRENE	2300						
	BENZO(A)ANTHRACENE	.87						
	CHRYSENE	87						
	BENZO(B)FLUORANTHENE	.87						
	BENZO(K)FLUORANTHENE	8.7						
	BENZO(A)PYRENE	.087						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

**Table 4
Summary of Analytical Results**

		PRA	0					
		PRA Description	RANDOM PCB					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASS007-40001	SGA-ASS008-40001		SGA-ASS009-40001		
		Depth - ft bgs	0 - .5	0 - .5		0 - .5		
		Collected Date	06/24/98	06/24/98		06/24/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087						
	BENZO(GHI)PERYLENE	2300						
	INDENO(1,2,3-C,D)PYRENE	.87						
P/PCB	AROCLOR-1254	1	0.40		ND		ND	
METAL	ANTIMONY, TOTAL	31						
	BARIUM, TOTAL	5500						
	BERYLLIUM, TOTAL	160						
	CADMIUM, TOTAL	39						
	CHROMIUM, TOTAL	230						
	LEAD, TOTAL	400						
	NICKEL, TOTAL	1600						
	SILVER, TOTAL	390						
	MERCURY, TOTAL	20						
	ARSENIC, TOTAL	.43						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

**Table 4
Summary of Analytical Results**

		PRA						
		PRA Description			TABLE 1 BACKGROUNDS			
		Sample Type			Normal Sample			
		Sample Id	SGA-ASS010-40001		SGA-ASU009-70001		SGA-ASU010-70001	
		Depth - ft bgs	0 - .5		5 - 5		5 - 5	
		Collected Date	06/24/98		06/24/98		06/24/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000			ND		ND	
	ETHYL BENZENE	7800			ND		ND	
	XYLENES (TOTAL)	1000000			ND		ND	
	ACETONE	7800			ND		ND	
BNA	NAPHTHALENE	1600			ND		ND	
	ACENAPHTHENE	4700			ND		ND	
	FLUORENE	3100			ND		ND	
	PHENANTHRENE	23000			ND		ND	
	ANTHRACENE	23000			ND		ND	
	FLUORANTHENE	3100			ND		ND	
	PYRENE	2300			ND		ND	
	BENZO(A)ANTHRACENE	.87			ND		ND	
	CHRYSENE	87			ND		ND	
	BENZO(B)FLUORANTHENE	.87			ND		ND	
	BENZO(K)FLUORANTHENE	8.7			ND		ND	
	BENZO(A)PYRENE	.087			ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

**Table 4
Summary of Analytical Results**

		PRA						
		PRA Description	TABLE 1 BACKGROUNDS					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASS010-40001	SGA-ASU009-70001		SGA-ASU010-70001		
		Depth - ft bgs	0 - .5	5 - 5		5 - 5		
		Collected Date	06/24/98	06/24/98		06/24/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087			ND		ND	
	BENZO(GHI)PERYLENE	2300			ND		ND	
	INDENO(1,2,3-C,D)PYRENE	.87			ND		ND	
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31			11.8 R		11.8 R	
	BARIUM, TOTAL	5500			76.6		100	
	BERYLLIUM, TOTAL	160			ND		ND	
	CADMIUM, TOTAL	39			12.6		13.9	
	CHROMIUM, TOTAL	230			9.9 J-		11.9 J-	
	LEAD, TOTAL	400			ND		ND	
	NICKEL, TOTAL	1600			16.5		21.0	
	SILVER, TOTAL	390			ND		ND	
	MERCURY, TOTAL	20			ND		ND	
	ARSENIC, TOTAL	.43			11.9	X	13.8	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA			1		2	
		PRA Description			PRA#1-500 GAL FORMER USED		PRA#2-2000 GAL FORMER DIES	
		Sample Type			Normal Sample		Normal Sample	
		Sample Id	SGA-ASU011-70001		SGA-ASU001-70001		SGA-ASU002-70001	
		Depth - ft bgs	5 - 5		0 - 0		0 - 0	
		Collected Date	06/24/98		06/25/98		06/25/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		0.018	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	ND					
BNA	NAPHTHALENE	1600	ND		ND		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	ND		ND		ND	
	PHENANTHRENE	23000	ND		ND		ND	
	ANTHRACENE	23000	ND		ND		ND	
	FLUORANTHENE	3100	ND		ND		ND	
	PYRENE	2300	ND		ND		ND	
	BENZO(A)ANTHRACENE	.87	ND		ND		ND	
	CHRYSENE	87	ND		ND		ND	
	BENZO(B)FLUORANTHENE	.87	ND		ND		ND	
	BENZO(K)FLUORANTHENE	8.7	ND		ND		ND	
	BENZO(A)PYRENE	.087	ND		ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA			1		2	
		PRA Description			PRA#1-500 GAL FORMER USED		PRA#2-2000 GAL FORMER DIES	
		Sample Type			Normal Sample		Normal Sample	
		Sample Id	SGA-ASU011-70001		SGA-ASU001-70001		SGA-ASU002-70001	
		Depth - ft bgs	5 - 5		0 - 0		0 - 0	
		Collected Date	06/24/98		06/25/98		06/25/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		ND	
	BENZO(GHI)PERYLENE	2300	ND		ND		ND	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		ND		ND	
P/PCB	AROCLOR-1254	1	ND		ND			
METAL	ANTIMONY, TOTAL	31	11.3 R					
	BARIUM, TOTAL	5500	14.4					
	BERYLLIUM, TOTAL	160	ND					
	CADMIUM, TOTAL	39	6.6					
	CHROMIUM, TOTAL	230	5.2 J-					
	LEAD, TOTAL	400	ND		ND			
	NICKEL, TOTAL	1600	ND					
	SILVER, TOTAL	390	ND					
	MERCURY, TOTAL	20	ND					
	ARSENIC, TOTAL	.43	30.4	X				

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

PRA	3		
PRA Description	PRA#3-FOUR 2000 GAL FORMER GASOLINE TANKS		
Sample Type	Normal Sample		
Sample Id	SGA-ASU003-70001	SGA-ASU004-70001	SGA-ASU005-70001
Depth - ft bgs	0 - 0	0 - 0	0 - 0
Collected Date	06/25/98	06/25/98	06/25/98
Laboratory	Recra Amherst	Recra Amherst	Recra Amherst
Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.	Civil + Environmental Cons.
Result Units	MG/KG	MG/KG	MG/KG

Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	0.015		0.009		0.033	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800						
BNA	NAPHTHALENE	1600	ND		ND		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	ND		ND		ND	
	PHENANTHRENE	23000	ND		ND		ND	
	ANTHRACENE	23000	ND		ND		ND	
	FLUORANTHENE	3100	ND		ND		ND	
	PYRENE	2300	ND		ND		ND	
	BENZO(A)ANTHRACENE	.87	ND		ND		ND	
	CHRYSENE	87	ND		ND		ND	
	BENZO(B)FLUORANTHENE	.87	ND		ND		ND	
	BENZO(K)FLUORANTHENE	8.7	ND		ND		ND	
	BENZO(A)PYRENE	.087	ND		ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	3					
		PRA Description	PRA#3-FOUR 2000 GAL FORMER GASOLINE TANKS					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASU003-70001	SGA-ASU004-70001		SGA-ASU005-70001		
		Depth - ft bgs	0 - 0	0 - 0		0 - 0		
		Collected Date	06/25/98	06/25/98		06/25/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		ND	
	BENZO(GHI)PERYLENE	2300	ND		ND		ND	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		ND		ND	
P/PCB	AROCLOR-1254	1						
METAL	ANTIMONY, TOTAL	31						
	BARIUM, TOTAL	5500						
	BERYLLIUM, TOTAL	160						
	CADMIUM, TOTAL	39						
	CHROMIUM, TOTAL	230						
	LEAD, TOTAL	400						
	NICKEL, TOTAL	1600						
	SILVER, TOTAL	390						
	MERCURY, TOTAL	20						
	ARSENIC, TOTAL	.43						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	4					
		PRA Description	PRA#4-FORMER RUSH CREEK DUMP					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASU006-70001	SGA-ASB004-40001		SGA-ASB004-70001		
		Depth - ft bgs	0 - 0	0 - 1		2.5 - 2.5		
		Collected Date	06/25/98	06/23/98		06/23/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800			ND		ND	
BNA	NAPHTHALENE	1600	ND		ND		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	ND		ND		ND	
	PHENANTHRENE	23000	ND		ND		ND	
	ANTHRACENE	23000	ND		ND		ND	
	FLUORANTHENE	3100	ND		ND		ND	
	PYRENE	2300	ND		ND		ND	
	BENZO(A)ANTHRACENE	.87	ND		ND		ND	
	CHRYSENE	87	ND		ND		ND	
	BENZO(B)FLUORANTHENE	.87	ND		ND		ND	
	BENZO(K)FLUORANTHENE	8.7	ND		ND		ND	
	BENZO(A)PYRENE	.087	ND		ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	4					
		PRA Description	PRA#4-FORMER RUSH CREEK DUMP					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASU006-70001	SGA-ASB004-40001		SGA-ASB004-70001		
		Depth - ft bgs	0 - 0	0 - 1		2.5 - 2.5		
		Collected Date	06/25/98	06/23/98		06/23/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		ND	
	BENZO(GHI)PERYLENE	2300	ND		ND		ND	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		ND		ND	
P/PCB	AROCLOR-1254	1			0.098		ND	
METAL	ANTIMONY, TOTAL	31			ND		ND	
	BARIUM, TOTAL	5500			114		117	
	BERYLLIUM, TOTAL	160			ND		ND	
	CADMIUM, TOTAL	39			12.6		10.0	
	CHROMIUM, TOTAL	230			12.6 J-		12.4 J-	
	LEAD, TOTAL	400			26.2 J+		ND	
	NICKEL, TOTAL	1600			15.8		15.5	
	SILVER, TOTAL	390			ND		ND	
	MERCURY, TOTAL	20			ND		ND	
	ARSENIC, TOTAL	.43			8.6 J-	X	8.1 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB004-70002		SGA-ASB005-40001		SGA-ASB005-70001	
		Depth - ft bgs	5 - 5		0 - 1		2 - 2	
		Collected Date	06/22/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	ND		ND		ND	
BNA	NAPHTHALENE	1600	ND		ND		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	ND		ND		ND	
	PHENANTHRENE	23000	ND		ND		11	
	ANTHRACENE	23000	ND		ND		3.4 J	
	FLUORANTHENE	3100	ND		ND		32	
	PYRENE	2300	ND		ND		25	
	BENZO(A)ANTHRACENE	.87	ND		ND		11	X
	CHRYSENE	87	ND		ND		9.1	
	BENZO(B)FLUORANTHENE	.87	ND		ND		9.9	X
	BENZO(K)FLUORANTHENE	8.7	ND		ND		11	X
	BENZO(A)PYRENE	.087	ND		ND		5.9 J	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
Category	Analyte	Sample Id	SGA-ASB004-70002		SGA-ASB005-40001		SGA-ASB005-70001	
		Depth - ft bgs	5 - 5		0 - 1		2 - 2	
		Collected Date	06/22/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
		Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		ND	
	BENZO(GHI)PERYLENE	2300	ND		ND		1.3 J	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		ND		1.6 J	X
	AROCLOR-1254	1	0.052		0.059		1.8	X
METAL	ANTIMONY, TOTAL	31	ND		ND		ND	
	BARIUM, TOTAL	5500	120		90.5		254	
	BERYLLIUM, TOTAL	160	ND		ND		ND	
	CADMIUM, TOTAL	39	12.7		13.2		33.2	
	CHROMIUM, TOTAL	230	12.5 J-		15.8 J-		30.2 J-	
	LEAD, TOTAL	400	ND		25.2 J+		252 J+	
	NICKEL, TOTAL	1600	17.3		19.2		27.1	
	SILVER, TOTAL	390	ND		ND		ND	
	MERCURY, TOTAL	20	ND		ND		2.1	
	ARSENIC, TOTAL	.43	10.2 J-	X	24.8 J-	X	10.0 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB005-70002		SGA-ASB006-40001		SGA-ASB006-70001	
		Depth - ft bgs	5 - 5		0 - 1		2.5 - 2.5	
		Collected Date	06/23/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	3.6		ND		ND	
	XYLENES (TOTAL)	1000000	9.7		ND		ND	
	ACETONE	7800	ND		ND		ND	
BNA	NAPHTHALENE	1600	210		ND		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	62		ND		ND	
	PHENANTHRENE	23000	280		ND		ND	
	ANTHRACENE	23000	92		ND		ND	
	FLUORANTHENE	3100	260		ND		1.4 J	
	PYRENE	2300	240		ND		ND	
	BENZO(A)ANTHRACENE	.87	150	X	ND		ND	
	CHRYSENE	87	130	X	ND		ND	
	BENZO(B)FLUORANTHENE	.87	120	X	0.53		2.0 J	X
	BENZO(K)FLUORANTHENE	8.7	75	X	0.60		1.9 J	
	BENZO(A)PYRENE	.087	110	X	ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB005-70002		SGA-ASB006-40001		SGA-ASB006-70001	
		Depth - ft bgs	5 - 5		0 - 1		2.5 - 2.5	
		Collected Date	06/23/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		ND	
	BENZO(GHI)PERYLENE	2300	79		ND		0.66 J	
	INDENO(1,2,3-C,D)PYRENE	.87	86	X	ND		ND	
P/PCB	AROCLOR-1254	1	12	X	0.043		0.70 J	
METAL	ANTIMONY, TOTAL	31	2140 J-	X	ND		ND	
	BARIUM, TOTAL	5500	842		97.4		82.2	
	BERYLLIUM, TOTAL	160	ND		ND		ND	
	CADMIUM, TOTAL	39	113	X	14.0		11.9	
	CHROMIUM, TOTAL	230	71.6 J-		11.2 J-		12.6 J-	
	LEAD, TOTAL	400	1650 J+	X	56.5 J+		55.8 J+	
	NICKEL, TOTAL	1600	85.7		24.4		26.0	
	SILVER, TOTAL	390	ND		42.0 J-		ND	
	MERCURY, TOTAL	20	1.3		0.38		0.31	
	ARSENIC, TOTAL	.43	38.9 J-	X	13.6 J-	X	10.9 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	5					
		PRA Description	PRA #5-FORMER DUMP					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASB006-70002	SGA-ASB007-40001		SGA-ASB007-70001		
		Depth - ft bgs	5 - 5	0 - 1		2.5 - 2.5		
		Collected Date	06/23/98	06/23/98		06/23/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	0.15 J		ND		ND	
BNA	NAPHTHALENE	1600	ND		ND		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	ND		ND		ND	
	PHENANTHRENE	23000	ND		ND		ND	
	ANTHRACENE	23000	ND		ND		ND	
	FLUORANTHENE	3100	ND		ND		ND	
	PYRENE	2300	ND		ND		ND	
	BENZO(A)ANTHRACENE	.87	ND		ND		ND	
	CHRYSENE	87	ND		ND		ND	
	BENZO(B)FLUORANTHENE	.87	ND		ND		ND	
	BENZO(K)FLUORANTHENE	8.7	ND		ND		ND	
	BENZO(A)PYRENE	.087	ND		ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	5					
		PRA Description	PRA #5-FORMER DUMP					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASB006-70002	SGA-ASB007-40001		SGA-ASB007-70001		
		Depth - ft bgs	5 - 5	0 - 1		2.5 - 2.5		
		Collected Date	06/23/98	06/23/98		06/23/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		ND	
	BENZO(GHI)PERYLENE	2300	ND		ND		ND	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		ND		ND	
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31	ND		ND		ND	
	BARIUM, TOTAL	5500	98.6		86.1		116	
	BERYLLIUM, TOTAL	160	ND		ND		ND	
	CADMIUM, TOTAL	39	9.6		13.0		5.3	
	CHROMIUM, TOTAL	230	9.6 J-		11.4 J-		5.4 J-	
	LEAD, TOTAL	400	ND		ND		34.1 J+	
	NICKEL, TOTAL	1600	ND		16.7		ND	
	SILVER, TOTAL	390	ND		ND		ND	
	MERCURY, TOTAL	20	ND		ND		ND	
	ARSENIC, TOTAL	.43	7.9 J-	X	11.4 J-	X	4.5 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB007-70002		SGA-ASB008-40001		SGA-ASB008-70001	
		Depth - ft bgs	5 - 5		0 - 1		2.5 - 2.5	
		Collected Date	06/23/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	ND		ND		ND	
BNA	NAPHTHALENE	1600	ND		1.1 J		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	ND		0.44 J		ND	
	PHENANTHRENE	23000	ND		3.4		ND	
	ANTHRACENE	23000	ND		0.95 J		ND	
	FLUORANTHENE	3100	ND		4.2		ND	
	PYRENE	2300	ND		3.8		ND	
	BENZO(A)ANTHRACENE	.87	ND		2.6	X	ND	
	CHRYSENE	87	ND		2.2		ND	
	BENZO(B)FLUORANTHENE	.87	ND		3.0	X	ND	
	BENZO(K)FLUORANTHENE	8.7	ND		1.6 J		ND	
	BENZO(A)PYRENE	.087	ND		2.4	X	ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB007-70002		SGA-ASB008-40001		SGA-ASB008-70001	
		Depth - ft bgs	5 - 5		0 - 1		2.5 - 2.5	
		Collected Date	06/23/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		0.39 J	X	ND	
	BENZO(GHI)PERYLENE	2300	ND		2.2		ND	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		2.1	X	ND	
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31	ND		ND		ND	
	BARIUM, TOTAL	5500	72.7		94.2		99.2	
	BERYLLIUM, TOTAL	160	ND		ND		ND	
	CADMIUM, TOTAL	39	13.5		32.0		7.9	
	CHROMIUM, TOTAL	230	14.7 J-		10.0 J-		8.1 J-	
	LEAD, TOTAL	400	ND		30.0 J+		ND	
	NICKEL, TOTAL	1600	19.9		14.5		ND	
	SILVER, TOTAL	390	ND		ND		ND	
	MERCURY, TOTAL	20	ND		ND		ND	
	ARSENIC, TOTAL	.43	13.8 J-	X	12.7 J-	X	7.5 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB008-70002		SGA-ASB009-40001		SGA-ASB009-70001	
		Depth - ft bgs	5 - 5		0 - 1		2.5 - 2.5	
		Collected Date	06/23/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	ND		ND		ND	
BNA	NAPHTHALENE	1600	ND		ND		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	ND		ND		ND	
	PHENANTHRENE	23000	ND		ND		ND	
	ANTHRACENE	23000	ND		ND		ND	
	FLUORANTHENE	3100	ND		ND		ND	
	PYRENE	2300	ND		ND		ND	
	BENZO(A)ANTHRACENE	.87	ND		ND		ND	
	CHRYSENE	87	ND		0.42		ND	
	BENZO(B)FLUORANTHENE	.87	ND		ND		ND	
	BENZO(K)FLUORANTHENE	8.7	ND		ND		ND	
	BENZO(A)PYRENE	.087	ND		ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB008-70002		SGA-ASB009-40001		SGA-ASB009-70001	
		Depth - ft bgs	5 - 5		0 - 1		2.5 - 2.5	
		Collected Date	06/23/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		ND	
	BENZO(GHI)PERYLENE	2300	ND		ND		ND	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		ND		ND	
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31	ND		ND		ND	
	BARIUM, TOTAL	5500	63.7		81.3		122	
	BERYLLIUM, TOTAL	160	ND		ND		ND	
	CADMIUM, TOTAL	39	11.6		20.7		7.4	
	CHROMIUM, TOTAL	230	9.5 J-		10.2 J-		7.4 J-	
	LEAD, TOTAL	400	ND		22.9 J+		101 J+	
	NICKEL, TOTAL	1600	15.6		17.2		ND	
	SILVER, TOTAL	390	ND		ND		ND	
	MERCURY, TOTAL	20	ND		ND		ND	
	ARSENIC, TOTAL	.43	11.9 J-	X	12.2 J-	X	9.5 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB009-70002		SGA-ASB011-40001		SGA-ASB011-70001	
		Depth - ft bgs	5 - 5		0 - 1		2.5 - 2.5	
		Collected Date	06/23/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		0.006		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	ND		ND		ND	
BNA	NAPHTHALENE	1600	ND		ND		ND	
	ACENAPHTHENE	4700	ND		ND		0.48	
	FLUORENE	3100	ND		ND		ND	
	PHENANTHRENE	23000	ND		1.2		2.6	
	ANTHRACENE	23000	ND		ND		0.81	
	FLUORANTHENE	3100	ND		1.7		3.7	
	PYRENE	2300	ND		1.8		5.0	
	BENZO(A)ANTHRACENE	.87	ND		0.84		2.6	X
	CHRYSENE	87	ND		0.81		2.7	
	BENZO(B)FLUORANTHENE	.87	ND		1.0	X	3.2	X
	BENZO(K)FLUORANTHENE	8.7	ND		ND		1.6	
	BENZO(A)PYRENE	.087	ND		0.70	X	2.8	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASB009-70002		SGA-ASB011-40001		SGA-ASB011-70001	
		Depth - ft bgs	5 - 5		0 - 1		2.5 - 2.5	
		Collected Date	06/23/98		06/23/98		06/23/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		0.42	X
	BENZO(GHI)PERYLENE	2300	ND		ND		1.8	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		0.42		1.9	X
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31	ND		ND		ND	
	BARIUM, TOTAL	5500	90.2		84.5		107	
	BERYLLIUM, TOTAL	160	ND		ND		ND	
	CADMIUM, TOTAL	39	9.0		14.6		29.9	
	CHROMIUM, TOTAL	230	8.4 J-		9.8 J-		14.6 J-	
	LEAD, TOTAL	400	ND		ND		33.6 J+	
	NICKEL, TOTAL	1600	12.2		14.3		16.6	
	SILVER, TOTAL	390	ND		ND		ND	
	MERCURY, TOTAL	20	ND		ND		ND	
	ARSENIC, TOTAL	.43	8.2 J-	X	12.2 J-	X	12.3 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	6					
		PRA Description	PRA#6-SEPTIC SYSTEM					
		Sample Type	Field Duplicate (Rep)			Normal Sample		
		Sample Id	SGA-ASB011-70002	SGA-ASU007-71001			SGA-ASU007-70001	
		Depth - ft bgs	5 - 5	5 - 5			5 - 5	
		Collected Date	06/23/98	06/24/98			06/24/98	
		Laboratory	Recra Amherst	Recra Amherst			Recra Amherst	
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.			Civil + Environmental Cons.	
		Result Units	MG/KG	MG/KG			MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	ND					
BNA	NAPHTHALENE	1600	ND					
	ACENAPHTHENE	4700	ND					
	FLUORENE	3100	ND					
	PHENANTHRENE	23000	ND					
	ANTHRACENE	23000	ND					
	FLUORANTHENE	3100	ND					
	PYRENE	2300	ND					
	BENZO(A)ANTHRACENE	.87	ND					
	CHRYSENE	87	ND					
	BENZO(B)FLUORANTHENE	.87	ND					
	BENZO(K)FLUORANTHENE	8.7	ND					
	BENZO(A)PYRENE	.087	ND					

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	6					
		PRA Description	PRA#6-SEPTIC SYSTEM					
		Sample Type	Field Duplicate (Rep)			Normal Sample		
		Sample Id	SGA-ASB011-70002	SGA-ASU007-71001			SGA-ASU007-70001	
		Depth - ft bgs	5 - 5	5 - 5			5 - 5	
		Collected Date	06/23/98	06/24/98			06/24/98	
		Laboratory	Recra Amherst	Recra Amherst			Recra Amherst	
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.			Civil + Environmental Cons.	
		Result Units	MG/KG	MG/KG			MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND					
	BENZO(GHI)PERYLENE	2300	ND					
	INDENO(1,2,3-C,D)PYRENE	.87	ND					
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31	ND					
	BARIUM, TOTAL	5500	90.3					
	BERYLLIUM, TOTAL	160	ND					
	CADMIUM, TOTAL	39	11.5					
	CHROMIUM, TOTAL	230	11.6					
	LEAD, TOTAL	400	ND					
	NICKEL, TOTAL	1600	15.4					
	SILVER, TOTAL	390	ND					
	MERCURY, TOTAL	20	ND					
	ARSENIC, TOTAL	.43	11.0	X				

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	7					
		PRA Description	PRA#7-RUSH CREEK					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASU008-70001	SGA-ASD001-30001		SGA-ASD002-30001		
		Depth - ft bgs	5 - 5	0 - 0		0 - 0		
		Collected Date	06/24/98	06/26/98		06/26/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800			ND		ND	
BNA	NAPHTHALENE	1600			ND		ND	
	ACENAPHTHENE	4700			ND		ND	
	FLUORENE	3100			ND		ND	
	PHENANTHRENE	23000			ND		ND	
	ANTHRACENE	23000			ND		ND	
	FLUORANTHENE	3100			ND		ND	
	PYRENE	2300			ND		ND	
	BENZO(A)ANTHRACENE	.87			ND		ND	
	CHRYSENE	87			ND		ND	
	BENZO(B)FLUORANTHENE	.87			ND		ND	
	BENZO(K)FLUORANTHENE	8.7			ND		ND	
	BENZO(A)PYRENE	.087			ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	7					
		PRA Description	PRA#7-RUSH CREEK					
		Sample Type	Normal Sample					
		Sample Id	SGA-ASU008-70001	SGA-ASD001-30001		SGA-ASD002-30001		
		Depth - ft bgs	5 - 5	0 - 0		0 - 0		
		Collected Date	06/24/98	06/26/98		06/26/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087			ND		ND	
	BENZO(GHI)PERYLENE	2300			ND		ND	
	INDENO(1,2,3-C,D)PYRENE	.87			ND		ND	
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31			ND		ND	
	BARIUM, TOTAL	5500			85.4 J		45.8	
	BERYLLIUM, TOTAL	160			2.4 J		1.2	
	CADMIUM, TOTAL	39			21.0 J		9.7 J-	
	CHROMIUM, TOTAL	230			10.5 J		6.7 J-	
	LEAD, TOTAL	400			ND		ND	
	NICKEL, TOTAL	1600			38.6 J		20.0	
	SILVER, TOTAL	390			ND		ND	
	MERCURY, TOTAL	20			ND		ND	
	ARSENIC, TOTAL	.43			11.7 J	X	6.8 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	8					
		PRA Description	PRA#8-FRAC TANK DRAINAGE CHANNEL					
		Sample Type	Field Duplicate (Rep)		Normal Sample			
		Sample Id	SGA-ASD004-31001		SGA-ASD004-30001		SGA-ASD005-30001	
		Depth - ft bgs	0 - 0		0 - 0		0 - 0	
		Collected Date	06/25/98		06/25/98		06/25/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	ND		ND		ND	
BNA	NAPHTHALENE	1600	ND		ND		ND	
	ACENAPHTHENE	4700	ND		ND		ND	
	FLUORENE	3100	ND		ND		ND	
	PHENANTHRENE	23000	ND		ND		ND	
	ANTHRACENE	23000	ND		ND		ND	
	FLUORANTHENE	3100	ND		ND		ND	
	PYRENE	2300	ND		ND		ND	
	BENZO(A)ANTHRACENE	.87	ND		ND		ND	
	CHRYSENE	87	ND		ND		ND	
	BENZO(B)FLUORANTHENE	.87	ND		ND		ND	
	BENZO(K)FLUORANTHENE	8.7	ND		ND		ND	
	BENZO(A)PYRENE	.087	ND		ND		ND	

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	8					
		PRA Description	PRA#8-FRAC TANK DRAINAGE CHANNEL					
		Sample Type	Field Duplicate (Rep)		Normal Sample			
		Sample Id	SGA-ASD004-31001		SGA-ASD004-30001		SGA-ASD005-30001	
		Depth - ft bgs	0 - 0		0 - 0		0 - 0	
		Collected Date	06/25/98		06/25/98		06/25/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND		ND		ND	
	BENZO(GHI)PERYLENE	2300	ND		ND		ND	
	INDENO(1,2,3-C,D)PYRENE	.87	ND		ND		ND	
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31	ND		ND		ND	
	BARIUM, TOTAL	5500	36.4		30.4		56.5	
	BERYLLIUM, TOTAL	160	ND		ND		ND	
	CADMIUM, TOTAL	39	11.2 J-		17.1 J-		15.0 J-	
	CHROMIUM, TOTAL	230	7.5 J-		8.9 J-		26.1 J-	
	LEAD, TOTAL	400	ND		ND		ND	
	NICKEL, TOTAL	1600	ND		ND		19.8	
	SILVER, TOTAL	390	ND		ND		ND	
	MERCURY, TOTAL	20	ND		ND		ND	
	ARSENIC, TOTAL	.43	12.7 J	X	23.4 J	X	19.4 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	9					
		PRA Description	PRA#9-REGULATOR LRP					
		Sample Type	Field Duplicate (Rep)					
		Sample Id	SGA-ASD006-30001	SGA-ASB010-41001		SGA-ASB010-71002		
		Depth - ft bgs	0 - 0	0 - 1		5 - 5		
		Collected Date	06/25/98	06/23/98		06/23/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800	ND					
BNA	NAPHTHALENE	1600	ND					
	ACENAPHTHENE	4700	ND					
	FLUORENE	3100	ND					
	PHENANTHRENE	23000	ND					
	ANTHRACENE	23000	ND					
	FLUORANTHENE	3100	ND					
	PYRENE	2300	ND					
	BENZO(A)ANTHRACENE	.87	ND					
	CHRYSENE	87	ND					
	BENZO(B)FLUORANTHENE	.87	ND					
	BENZO(K)FLUORANTHENE	8.7	ND					
	BENZO(A)PYRENE	.087	ND					

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	9					
		PRA Description	PRA#9-REGULATOR LRP					
		Sample Type	Field Duplicate (Rep)					
		Sample Id	SGA-ASD006-30001	SGA-ASB010-41001		SGA-ASB010-71002		
		Depth - ft bgs	0 - 0	0 - 1		5 - 5		
		Collected Date	06/25/98	06/23/98		06/23/98		
		Laboratory	Recra Amherst	Recra Amherst		Recra Amherst		
		Sample Collector	Civil + Environmental Cons.	Civil + Environmental Cons.		Civil + Environmental Cons.		
		Result Units	MG/KG	MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087	ND					
	BENZO(GHI)PERYLENE	2300	ND					
	INDENO(1,2,3-C,D)PYRENE	.87	ND					
P/PCB	AROCLOR-1254	1	ND		ND		0.050	
METAL	ANTIMONY, TOTAL	31	ND					
	BARIUM, TOTAL	5500	95.5 J					
	BERYLLIUM, TOTAL	160	ND					
	CADMIUM, TOTAL	39	16.1 J					
	CHROMIUM, TOTAL	230	11.9 J					
	LEAD, TOTAL	400	ND					
	NICKEL, TOTAL	1600	28.9 J					
	SILVER, TOTAL	390	ND					
	MERCURY, TOTAL	20	ND					
	ARSENIC, TOTAL	.43	9.6 J	X				

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

PRA		PRA Description						
Sample Type		Normal Sample						
Sample Id		SGA-ASB010-40001		SGA-ASB010-70001		SGA-ASB010-70002		
Depth - ft bgs		0 - 1		2.5 - 2.5		5 - 5		
Collected Date		06/23/98		06/23/98		06/23/98		
Laboratory		Recra Amherst		Recra Amherst		Recra Amherst		
Sample Collector		Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.		
Result Units		MG/KG		MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800						
BNA	NAPHTHALENE	1600						
	ACENAPHTHENE	4700						
	FLUORENE	3100						
	PHENANTHRENE	23000						
	ANTHRACENE	23000						
	FLUORANTHENE	3100						
	PYRENE	2300						
	BENZO(A)ANTHRACENE	.87						
	CHRYSENE	87						
	BENZO(B)FLUORANTHENE	.87						
	BENZO(K)FLUORANTHENE	8.7						
	BENZO(A)PYRENE	.087						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

PRA		PRA Description						
Sample Type		Normal Sample						
Sample Id		SGA-ASB010-40001		SGA-ASB010-70001		SGA-ASB010-70002		
Depth - ft bgs		0 - 1		2.5 - 2.5		5 - 5		
Collected Date		06/23/98		06/23/98		06/23/98		
Laboratory		Recra Amherst		Recra Amherst		Recra Amherst		
Sample Collector		Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.		
Result Units		MG/KG		MG/KG		MG/KG		
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087						
	BENZO(GHI)PERYLENE	2300						
	INDENO(1,2,3-C,D)PYRENE	.87						
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31						
	BARIUM, TOTAL	5500						
	BERYLLIUM, TOTAL	160						
	CADMIUM, TOTAL	39						
	CHROMIUM, TOTAL	230						
	LEAD, TOTAL	400						
	NICKEL, TOTAL	1600						
	SILVER, TOTAL	390						
	MERCURY, TOTAL	20						
	ARSENIC, TOTAL	.43						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	10					
		PRA Description	PRA#10-FORMER PIPEYARD					
		Sample Type	Field Duplicate (Rep)		Normal Sample			
		Sample Id	SGA-ASS001-41001		SGA-ASS001-40001		SGA-ASS002-40001	
		Depth - ft bgs	0 - 1		0 - 1		0 - 1	
		Collected Date	06/24/98		06/24/98		06/24/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800						
BNA	NAPHTHALENE	1600						
	ACENAPHTHENE	4700						
	FLUORENE	3100						
	PHENANTHRENE	23000						
	ANTHRACENE	23000						
	FLUORANTHENE	3100						
	PYRENE	2300						
	BENZO(A)ANTHRACENE	.87						
	CHRYSENE	87						
	BENZO(B)FLUORANTHENE	.87						
	BENZO(K)FLUORANTHENE	8.7						
	BENZO(A)PYRENE	.087						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA	10					
		PRA Description	PRA#10-FORMER PIPEYARD					
		Sample Type	Field Duplicate (Rep)		Normal Sample			
		Sample Id	SGA-ASS001-41001		SGA-ASS001-40001		SGA-ASS002-40001	
		Depth - ft bgs	0 - 1		0 - 1		0 - 1	
		Collected Date	06/24/98		06/24/98		06/24/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087						
	BENZO(GHI)PERYLENE	2300						
	INDENO(1,2,3-C,D)PYRENE	.87						
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31						
	BARIUM, TOTAL	5500						
	BERYLLIUM, TOTAL	160						
	CADMIUM, TOTAL	39						
	CHROMIUM, TOTAL	230						
	LEAD, TOTAL	400						
	NICKEL, TOTAL	1600						
	SILVER, TOTAL	390						
	MERCURY, TOTAL	20						
	ARSENIC, TOTAL	.43						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASS003-40001		SGA-ASS004-40001		SGA-ASS005-40001	
		Depth - ft bgs	0 - 1		0 - 1		0 - 1	
		Collected Date	06/24/98		06/24/98		06/24/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800						
BNA	NAPHTHALENE	1600						
	ACENAPHTHENE	4700						
	FLUORENE	3100						
	PHENANTHRENE	23000						
	ANTHRACENE	23000						
	FLUORANTHENE	3100						
	PYRENE	2300						
	BENZO(A)ANTHRACENE	.87						
	CHRYSENE	87						
	BENZO(B)FLUORANTHENE	.87						
	BENZO(K)FLUORANTHENE	8.7						
	BENZO(A)PYRENE	.087						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA						
		PRA Description						
		Sample Type						
		Sample Id	SGA-ASS003-40001		SGA-ASS004-40001		SGA-ASS005-40001	
		Depth - ft bgs	0 - 1		0 - 1		0 - 1	
		Collected Date	06/24/98		06/24/98		06/24/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087						
	BENZO(GHI)PERYLENE	2300						
	INDENO(1,2,3-C,D)PYRENE	.87						
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31						
	BARIUM, TOTAL	5500						
	BERYLLIUM, TOTAL	160						
	CADMIUM, TOTAL	39						
	CHROMIUM, TOTAL	230						
	LEAD, TOTAL	400						
	NICKEL, TOTAL	1600						
	SILVER, TOTAL	390						
	MERCURY, TOTAL	20						
	ARSENIC, TOTAL	.43						

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA			11		12	
		PRA Description			PRA#11-CATCH BASIN HEADW		PRA#12-DRY WELL	
		Sample Type			Normal Sample		Normal Sample	
		Sample Id	SGA-ASS006-40001		SGA-ASD008-30001		SGA-ASD009-30001	
		Depth - ft bgs	0 - 1		0 - 0		0 - 0	
		Collected Date	06/24/98		06/26/98		06/26/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
VOA	TOLUENE	16000	ND		ND		ND	
	ETHYL BENZENE	7800	ND		ND		ND	
	XYLENES (TOTAL)	1000000	ND		ND		ND	
	ACETONE	7800					ND	
BNA	NAPHTHALENE	1600			ND		ND	
	ACENAPHTHENE	4700			ND		1.1 J	
	FLUORENE	3100			ND		ND	
	PHENANTHRENE	23000			ND		26	
	ANTHRACENE	23000			ND		2.0 J	
	FLUORANTHENE	3100			ND		42	
	PYRENE	2300			ND		36	
	BENZO(A)ANTHRACENE	.87			ND		14	X
	CHRYSENE	87			ND		22	
	BENZO(B)FLUORANTHENE	.87			ND		23	X
	BENZO(K)FLUORANTHENE	8.7			ND		13	X
	BENZO(A)PYRENE	.087			ND		15	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

Table 4
Summary of Analytical Results

		PRA			11		12	
		PRA Description			PRA#11-CATCH BASIN HEADW		PRA#12-DRY WELL	
		Sample Type			Normal Sample		Normal Sample	
		Sample Id	SGA-ASS006-40001		SGA-ASD008-30001		SGA-ASD009-30001	
		Depth - ft bgs	0 - 1		0 - 0		0 - 0	
		Collected Date	06/24/98		06/26/98		06/26/98	
		Laboratory	Recra Amherst		Recra Amherst		Recra Amherst	
		Sample Collector	Civil + Environmental Cons.		Civil + Environmental Cons.		Civil + Environmental Cons.	
		Result Units	MG/KG		MG/KG		MG/KG	
Category	Analyte	Action Level	Result Flag	> CAL*	Result Flag	> CAL*	Result Flag	> CAL*
	DIBENZO(A,H)ANTHRACENE	.087			ND		3.7 J	X
	BENZO(GHI)PERYLENE	2300			ND		15	
	INDENO(1,2,3-C,D)PYRENE	.87			ND		14	X
P/PCB	AROCLOR-1254	1	ND		ND		ND	
METAL	ANTIMONY, TOTAL	31					ND	
	BARIUM, TOTAL	5500					72.9	
	BERYLLIUM, TOTAL	160					ND	
	CADMIUM, TOTAL	39					12.6 J-	
	CHROMIUM, TOTAL	230					16.0 J-	
	LEAD, TOTAL	400					80.0	
	NICKEL, TOTAL	1600					17.3	
	SILVER, TOTAL	390					ND	
	MERCURY, TOTAL	20					ND	
	ARSENIC, TOTAL	.43					10.4 J-	X

Notes:

* "> CAL" equals "X" when reported value is above characterization action level for this locale.

J flag - Numerical value is an estimated quantity.

ND indicates Non-Detect

Blank cells in result column indicate an analysis was not performed for that analyte.

APPENDIX H
SITE BACKGROUND CALCULATIONS

SITE BACKGROUND CALCULATIONS

The following table presents the site background calculation for detected CWP Table 1 metals.

BACKGROUND SAMPLE	BARIUM (MG/KG)	CADMIUM (MG/KG)	CHROMIUM (MG/KG)	NICKEL (MG/KG)	ARSENIC (MG/KG)
SGA-ASU009-70001	76.6	12.6	9.9	16.5	11.9
SGA-ASU010-70001	100	13.9	11.9	21.0	13.8
SGA-ASU011-70001	14.4	6.6	5.2	5.6*	30.4
Total	191.0	33.1	27.0	43.1	56.1
Average	63.7	11.0	9.0	14.4	18.7
Multiplied by 2	127.4	22.0	18.0	28.8	37.4

NOTES:

1. Calculations based on: "Data Collection and Evaluation, Human Health Risk Assessment Bulletin, No. 2., Supplemental Guidance to RAGs," Office Technical Services, U.S. EPA Region IV, October 1996.
2. * : Half of laboratory reporting limit.

APPENDIX I
SOIL BORING LOGS

**Civil & Environmental Consultants, Inc.**

Cincinnati, OH Pittsburgh, PA
(513) 985-0226 • (800) 759-5814 (412) 921-3402 • (800) 385-2324

**Columbia Gas Transmission
Sugar Grove
Area Office****Sugar Grove, Ohio**

JOB NO.: 98320-0250

LOG OF ASB004

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/23/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HMU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.0	0-1		5		Brown, clayey SILT (ML) softening and moistening at depth				
		2-3								
1.0	1.0	4-5				Brown, sand (SP), loose, unsorted, moist Boring terminated at 5 feet				

**Civil & Environmental Consultants, Inc.**

Cincinnati, OH Pittsburgh, PA
(513) 885-0226 • (800) 758-5814 (412) 921-3402 • (800) 385-2324

**Columbia Gas Transmission
Sugar Grove
Area Office****Sugar Grove, Ohio**

JOB NO.: 88320-0080

LOG OF ASB005

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/23/98


INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HMU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	2.0	0-1				Brown, clay, med. stiff, softening and moistening with depth (FILL)				
		1.5-2				Wood debris No Recovery				
	1.0	2.0				4.5-5	5	Wood debris (FILL) Tan, sand, odor, wet (FILL) Black burned material (FILL) Black, sandy clay, odor, wet to moist (FILL) No recovery		
15										
						Boring terminated at 8 feet				
				10						
				15						
				20						
				25						



Civil & Environmental Consultants, Inc.

Cincinnati, OH Pittsburgh, PA
(513) 985-0226 • (800) 759-5814 (412) 921-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASB008

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 8/23/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4" Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.5	0-1				Brown, clayey silt, moistening and softening at depth. Concrete and crushed gravel fragments through interval. Staining and slight odor at 4.5 feet. (FILL)				
		2-3								
		4-5								
1.0	1.0	4-5		5		Black stained inclusion Boring terminated at 5 feet				
				10						
				15						
				20						
				25						

**Civil & Environmental Consultants, Inc.**

Cincinnati, OH Pittsburgh, PA
(513) 985-0228 • (800) 759-5814 (412) 921-3402 • (800) 365-2324

**Columbia Gas Transmission
Sugar Grove
Area Office****Sugar Grove, Ohio**

JOB NO.: 98320-0280

LOG OF ASB007

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. — Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/23/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe — 4" Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS



DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.0	0-1		5		Brown, sand-silt-gravel mix (GM), loose, wet				
						Brown, silty SAND (SM), loose, very wet				
		2-3								
1.0	1.0	4-5								
						Boring terminated at 5 feet				
				10						
				15						
				20						
				25						

**Civil & Environmental Consultants, Inc.**

Cincinnati, OH Pittsburgh, PA
(513) 885-0228 • (800) 759-5814 (412) 821-3402 • (800) 385-2324

**Columbia Gas Transmission
Sugar Grove
Area Office****Sugar Grove, Ohio****JOB NO.: 98320-0280****LOG OF ASB008****Sheet 1 of 1****LOGGED BY:** (b) (4)**GROUND SURFACE ELEVATION:** N/A**DRILLER:** Subsurface, Inc. - Tim Mihal**TOP OF CASING ELEVATION:** N/A**DATE DRILLED:** 6/23/98**INITIAL WATER LEVEL:** N/A ft. BGS**DATE:****DRILL METHOD:** Geoprobe - 4' Macro Sampler**STATIC WATER LEVEL:** N/A ft. BGS**DATE:**

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.5	0-1		5		Brown, fine sandy loam, crushed gravel interspersed in 0-1 foot interval, loose				
		2-3				Brown, fine sandy clay, soft to medium stiff, wet				
1.0	1.0	4-5				Boring terminated at 5 feet				

Cincinnati, OH Pittsburgh, PA
(513) 385-0228 • (800) 758-5814 (412) 921-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASE009

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. – Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/23/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNW (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.5	0-1		5		Brown, sand-silt-gravel mix (GM), loose, wet				
		2-3			Brown, silty SAND (SM), loose, wet					
	1.0	1.0			4-5	Boring terminated at 5 feet				



Civil & Environmental Consultants, Inc.

Cincinnati, OH

Pittsburgh, PA

(513) 985-0228 • (800) 759-5814

(412) 821-3402 • (800) 365-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASB010

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/23/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4" Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNW (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.2	0-1		5		Brown, clayey silt (ML), loose, wet				
		2-3								
1.0	1.0	4-5				Boring terminated at 5 feet				
				10						
				15						
				20						
				25						



Civil & Environmental Consultants, Inc.

Cincinnati, OH Pittsburgh, PA
(513) 885-0226 • (800) 759-5814 (412) 921-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASB011

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/23/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.1	0-1		5		Brown, sand-silt-gravel mix (GM), loose, wet				
		2-3				Brown, silty sand (SM), loose, wet				
1.0	1.0	4-5				Boring terminated at 5 feet				
				10						
				15						
				20						
				25						

**Civil & Environmental Consultants, Inc.**

Cincinnati, OH Pittsburgh, PA
(513) 885-0226 • (800) 758-5814 (412) 921-3402 • (800) 385-2324

**Columbia Gas Transmission
Sugar Grove
Area Office****Sugar Grove, Ohio**

JOB NO.: 98320-0280

LOG OF ASUG001

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/25/98




INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (%)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description					
3.0	2.5	8.5-10		5		Brown, coarse sand and gravel, well sorted, loose, wet (FILL)					
3.0	2.5										
3.0	2.0			10							
3.0	2.0			15							
						Boring terminated at 16 feet					
				20							
				25							



Civil & Environmental Consultants, Inc.

Cincinnati, OH Pittsburgh, PA
(513) 985-0228 • (800) 758-5814 (412) 921-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASUP02

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/25/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
2.0	3.0					Orange-brown, sandy gravel, loose, moist (FILL)				
2.0	3.0			5						
2.0	2.7	9-10		10		Brown, coarse to medium SAND (SM), rounded pebbles, very loose, wet				
2.0	2.5			15						
				20						
				25		Boring terminated at 18 feet				



Civil & Environmental Consultants, Inc.

Cincinnati, OH

Pittsburgh, PA

(513) 985-0228 • (800) 759-5814

(412) 921-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASU003

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 8/25/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description					
1.0	3.0					Light gray silty SAND (SM), loose, slightly moist					
						Light brown to brown medium SAND (SW), loose, moist to wet					
1.0	3.0	5-8		5		Brown, clayey SAND (SC), soft, wet					
1.0	1.2										
				10		Geoprobe refusal at 9.4 feet					
				15							
				20							
				25							



Civil & Environmental Consultants, Inc.

Cincinnati, OH Pittsburgh, PA
(513) 985-0226 • (800) 759-5814 (412) 921-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASU005

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/25/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.0					Brown, sandy gravel, stiff, moist (FILL)				
1.0	3.0	5-8		5						
1.0	1.2			10		Brown, SAND (SP), loose, wet				
				15		Boring terminated at 12 feet				
				20						
				25						

**Civil & Environmental Consultants, Inc.**

Cincinnati, OH Pittsburgh, PA
(513) 885-0228 • (800) 759-5814 (412) 821-3402 • (800) 385-2324

**Columbia Gas Transmission
Sugar Grove
Area Office****Sugar Grove, Ohio**

JOB NO.: 98320-0280

LOG OF ASU006

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/25/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
1.0	3.0					Light gray, sandy gravel, loose, slightly moist (FILL)				
						Light brown, silt-sand-gravel mix, loose, moist (FILL)				
1.0	3.3	5-8		5						
						Brown, well sorted, coarse SAND (SW), very loose, wet				
1.0	2.7			10						
						Boring terminated at 12 feet				
				15						
				20						
				25						



Civil & Environmental Consultants, Inc.

Cincinnati, OH

(513) 985-0226 • (800) 759-5814

Pittsburgh, PA

(412) 921-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF 45U007

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/24/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
0.5	2.0					Brown, clay-sand-gravel mix, loose to very loose (FILL)				
						No recovery				
0.5	2.0	5-8		5		Brown, clay-sand-gravel mix, loose to very loose (FILL)				
						Black, clay-sand-gravel mix, loose, organic odor, wet (FILL)				
						No recovery				
				10		Boring terminated at 8 feet				
				15						
				20						
				25						



Civil & Environmental Consultants, Inc.

Cincinnati, OH Pittsburgh, PA
(513) 985-0228 • (800) 759-5814 (412) 921-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASU008

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/24/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
0.5	3.5				++++	Crushed rock (FILL)				
					++++	Dark gray-brown, silty clay, loose, slightly moist (FILL)				
					////	Brown, silty CLAY (CL), soft, moist to wet				
						No recovery				
0.5	2.0	5-8		5	////	Light brown to tan, silty CLAY (CL), very soft, wet				
						Boring terminated at 8 feet				
				10						
				15						
				20						
				25						

**Civil & Environmental Consultants, Inc.**

Cincinnati, OH Pittsburgh, PA
(513) 985-0228 • (800) 759-5814 (412) 921-3402 • (800) 385-2324

**Columbia Gas Transmission
Sugar Grove
Area Office****Sugar Grove, Ohio**

JOB NO.: 98320-0280

LOG OF ASU009

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 6/24/98


INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
0.5	4.0	5-8		5		Brown, silty CLAY (CL), loose, increasing moisture and lightening in color with depth becoming med. soft.				
0.5	2.0					Light brown, sandy CLAY (CL), moist to wet, very soft				
						Boring terminated at 8 feet				
				10						
				15						
				20						
				25						



Civil & Environmental Consultants, Inc.

Cincinnati, OH Pittsburgh, PA
(513) 885-0228 • (800) 759-5814 (412) 821-3402 • (800) 385-2324

Columbia Gas Transmission
Sugar Grove
Area Office

Sugar Grove, Ohio

JOB NO.: 98320-0280

LOG OF ASU010

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 8/24/98

INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description				
0.5	4.0					Dark brown, CLAY (CL), med. stiff, increasing in moisture with depth below 1 foot and slightly lightening in hue. Small percentage of silt and fine sand in intermittent intervals.				
0.5	2.0	5-6		5		Brown, CLAY (CL), medium stiff, slightly moist				
						Boring terminated at 8 feet				
				10						
				15						
				20						
				25						

**Civil & Environmental Consultants, Inc.**

Cincinnati, OH Pittsburgh, PA
(513) 985-0228 • (800) 759-5814 (412) 921-3402 • (800) 385-2324

**Columbia Gas Transmission
Sugar Grove
Area Office****Sugar Grove, Ohio**

JOB NO.: 98320-0280

LOG OF ASU011

Sheet 1 of 1

LOGGED BY: (b) (4)

GROUND SURFACE ELEVATION: N/A

DRILLER: Subsurface, Inc. - Tim Mihal

TOP OF CASING ELEVATION: N/A

DATE DRILLED: 8/24/98






INITIAL WATER LEVEL: N/A ft. BGS

DATE:

DRILL METHOD: Geoprobe - 4' Macro Sampler

STATIC WATER LEVEL: N/A ft. BGS

DATE:

HNU (ppm)	Recovery (ft)	Sample Interval	Sample ID	Depth (ft.)	Graphic Log	Materials Description					
0.5	4.0					Brown, silty CLAY (CL), dry, medium loose to medium dense					
						Greyish, light brown, SAND (SM) lens, slightly moist					
						Light brown, clayey SILT (ML), stiff, slightly moist, gray mottles at 4 feet					
0.5	2.0	5-8		5		Light brown, clayey SILT (ML), gray mottles, very stiff					
						Brown, silty SAND (SM), medium dense to medium loose, slightly moist					
						Boring terminated at 8 feet					
				10							
				15							
				20							
				25							

**SUMMARY OF SURFACE SOIL BORINGS
SUGAR GROVE AREA OFFICE
SUGAR GROVE, OHIO**

Location	Location	Analytes ¹	HNU PID (ppm)	Description ^{2,3}
ASS001	12	BTEX, PCBs	0.0	Brown, sandy loam (CL), no odor or staining
ASS002	12	BTEX, PCBs	0.0	6 inch brown, crushed gravel with silty sand component, 12 inch brown silty sand, loose to med. dense; 2 inch light brown, sandy loam, med. stiff
ASS003	12	BTEX, PCBs	3.0	Brown, sandy loam (CL), med. dense, black unknown inclusion
ASS004	12	BTEX, PCBs	3.0	Brown, loam (CL), med. dense, dry, black inclusion at 3 inch bgs, no odor or staining
ASS005	12	BTEX, PCBs	0.0	Brown, loam (CL), dense, med. dry, no odors or staining
ASS006	12	BTEX, PCBs	0.0	Brown, silty CLAY (CL), stiff, med. dry to slightly moist at bottom of interval, no odors or staining
ASS007	PCB ⁴	PCBs	0.0	Brown, loamy CLAY (CL), med. stiff, med. moist, some pebbles in matrix, no odors or staining, some small black inclusions
ASS008	PCB ⁴	PCBs	0.0	Brown, silty clay, moist at bottom of interval, no odors or staining (FILL)
ASS009	PCB ⁴	PCBs	0.0	6 inch crushed gravel; 12 inch brown, gray, and black, clayey fill material, no obvious stains, no odors (FILL)
ASS010	PCB ⁴	PCBs	0.0	Cover is crushed gravel; brown, loose, gravelly fine SAND (SP), no odor, no staining

Notes:

1. For surface soil samples, the sample portion for PCB and metal analyses was collected from 0-0.5 foot and the sample portion for VOCs and SVOCs (if necessary) analyses was collected from 0.5-1 foot.
2. Abbreviations in parentheses are the group symbols from the Unified Soil Classification System.
3. Samples collected by Geoprobe borings (Subsurface, Inc.) and logged by C. Scott Titzel (CEC)
4. PCB background random sample